

Plan of Action

Addendum 1

January 27, 2017

The following addendum is issued for the Carson Valley Middle School asbestos abatement that is scheduled for the spring and summer of 2017. Compliance with this addendum and the abatement “Plan of Action” will be required.

****April 17, 2017**

**Building A, Area 100, Art Room and Kitchen Ceiling
Building B, Area 200, Teacher’s Lounge and Storage Rooms**

The asbestos abatement in these areas must be completed between April 17, 2017 and April 24, 2017.

All of the flooring abatement will require the asbestos abatement contractor to remove all the cove base.

The asbestos abatement in Building A, Area 100, Art Room and Kitchen will also include the removal of approximately 150 square feet of water damaged ceiling materials within the Kitchen. The Kitchen ceiling abatement area will be included in the Art Room containment area.

The abatement in Building B, Area 200, Teacher’s Lounge and Storage Rooms involves the sheet rock ceilings and flooring materials only. All of the walls are concrete block.

****June 12, 2017**

**Building A, Area 100, Administrative Offices and Corridor
Building B, Area 200, Nurse’s Office and Restrooms**

All of the flooring abatement will require the asbestos abatement contractor to remove all the cove base.

The asbestos abatement in Building A, Area 100 Administrative Offices and Corridor will require the abatement contractor to remove all of the lockers and bases in order to access any flooring materials under them. The owner will provide metal recycling dumpsters for the metal lockers.

The asbestos abatement in Building B, Area 200, Nurse’s Office and Restrooms involves the sheet rock ceilings and flooring materials only. All of the walls are concrete block.

****June 26, 2017**

**Building A, Area 100, East Corridor
Building A, Area 200, Corridor
Building B, Area 200, Corridors**

All of the flooring abatement will require the asbestos abatement contractor to remove all the cove base.

The asbestos abatement in these areas will require the abatement contractor to remove all of the lockers and bases in order to access any flooring materials under them. The owner will provide metal recycling dumpsters for the metal lockers.

End of Addendum 1